

EVO Condominium Project



Type of Project	Construction of under ground car parking structure
Purpose of Piling	Permanent wall during 100 years for under ground parking structure
Site Location	1155 South Grand Avenue, Los Angeles, CA, U.S.A.
Duration of Work	February to April 2006
Client	Howards Wright Construction Co
Piling Contractor	Giken America Corporation
Press-in System	Press-in Method with Simultaneous Augering
Press-in Material	Z Sheet Pile AZ36 L=50Ft.(15.24m) 393 pices
Press-in Machinery	Super Crush Z Piler SCZ-675SM x 2 units
Method Description	Installation into very dense coarse sand with gravel and cobbles. (Max. SPT value is more than 500)

