

Press-in Method with Water Jetting



| | |
|--------------------|---|
| Type of Project | Hospital Basement |
| Purpose of Piling | Retaining wall for basement |
| Site Location | New Romford Hospital, London, U.K. |
| Duration of Work | August, 2003 to April, 2004 |
| Client | NHS |
| Piling Contractor | Giken Europe Corporation |
| Press-in System | Pre-Augering, Press-In with Water Jetting |
| Press-in Material | U Sheet Pile LX38 L=15.3m |
| Press-in Machinery | U Piler UP150 |
| Method Description | Silent Piling Method and space saving technique were required |

