



Non-staging Press-in Method





Type of Project	Flood Defense
Purpose of Piling	Reinforcement of the existing embankment
Site Location	Bridgwater, UK
Duration of Work	May to August, 2004
Client	Environment Agency
Piling Contractor	GIKEN EUROPE B.V.
Press-in System	Non-staging Press-in Method
Press-in Material	U Sheet Pile Larssen LX 12/16 L=5.0/7.5m 1250nos.
Press-in Machinery	U Piler SW100, Clamp Crane 2.9ton, Pile Runner, Unit Runner
Method Description	No traffic disruption (Road closure) on the public road. Silent and vibration-free operation.

