




West Street, Erith, Kent











Type of Project	Property Development (4 to 5 storey flat)
Purpose of Piling	Permanent Retaining Wall
Site Location	Erith, Kent, U.K.
Duration of Work	From Nov. 2005 to Dec. 2005
Employer	Orbit Housing Association
Consultant Engineer	Powell Tolner & Associates
Main Contractor	Hill Partnerships Ltd.

Piling Contractor	Giken Europe B. V.
Press-in System	Press-in Method with Simultaneous Augering
Press-in Material	Crimped Z piles AZ46/ 50 L=9.5-12.5m 36nos.
Press-in Machinery	Super Crush Z Piler SCZ-675WM
Method Description	Rapid construction based on "One step approach" - temporary free works Silent and vibration-free operation Press-in work into flint mixed chalk