




Furukawa River Restoration Project











| Type of Project | Restoration work of river embankment |
|--------------------|-----------------------------------------------------------------|
| Purpose of Piling | Retaining wall |
| Site Location | Tokyo, Japan |
| Duration of Work | Mar 2007 - Jun 2007 |
| Client | Construction Office of Tokyo Metropolitan Government |
| Piling Contractor | Giken Seko Co.,Ltd. |
| Press-in System | Gyropress Method |
| Press-in Material | Tubular Pile, D 1000mm, to=12mm, L=13.5m (3-5 joints), no=48 |
| Press-in Machinery | Gyro Clear Piler |
| Method Description | Piling under overhead obstruction. (6.5m) |
| | Coring through existing footing structures by Gyropress Method. |
| | No temporary work platform is required. |

